

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-01030-00-01
Spot: SENENENW Sec/Twnshp/Rge: 9-25S-18E
4780 feet from S Section Line, 2910 feet from E Section Line
Lease Name: LARSON Well #: A 3
County: ALLEN Total Vertical Depth: 630 feet

Operator License No.: 33221
Op Name: ROXANNA PIPELINE, INC.
Address: 4600 GREENVILLE AVE STE 200
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	630	0	
SURF	7	20	0	

35

Well Type: EOR UIC Docket No: E21612.6 Date/Time to Plug: 07/25/2008 10:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION CO. Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO 630' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGIN PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 07/25/2008 10:30 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 1000 PSI.

RECEIVED
KCC DISTRICT #3

JUL 30 2008 CPT

CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
606	614	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 04 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED

Remarks:

Plugged through: CSG

DATE 8-18-08
INV. NO. 2009060261

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)