

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22263-00-00
Spot: NESWNE Sec/Twnshp/Rge: 15-26S-12W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: STALCUP Well #: 1
County: PRATT Total Vertical Depth: 4350 feet

Operator License No.: 3959
Op Name: SIROKY OIL MANAGEMENT
Address: PO BOX 464
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3800		
CIBP		4145		
PROD	4.5	4340	1500	WITH 175 SX CMT
SURF	8.625	377		WITH 200 SX CMT

141.38

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/24/2008 5:15 PM
Plug Co. License No.: 33093 Plug Co. Name: GENESIS WELL SERVICE, INC.
Proposal Rcvd. from: BRIAN SIROKY Company: GENESIS WELL SERVICE, INC. Phone: (620) 672-5625

Proposed Plugging Method: SET CIBP @ 2975' WITH 2 SX CMT OR SAND BACK TO 2975' WITH 4 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/24/2008 6:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 2975' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. RUN 2 3/8" TBG IN TO PLUG THROUGH. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4175	4180		
4107	4111		
4096	4100		
3692	3696		
3487	3490		
3129	3130		
3115	3115		
3029	3031		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 04 2008
CONSERVATION DIVISION
WICHITA, KS


Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

INVOICED

DATE 8-18-08
INV. NO. 2009060263

District: 01



Signed Stephan J. Pfeifer
(TECHNICIAN)