

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-19426-00-01  
Spot: SWNE Sec/Twnshp/Rge: 3-25S-17E  
3300 feet from S Section Line, 2004 feet from E Section Line  
Lease Name: PIQUA GAS STORAGE Well #: 10  
County: WOODSON Total Vertical Depth: 929 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	900	0	200 SX
SURF	10	16	0	

35

Well Type: GSW UIC Docket No: Date/Time to Plug: 07/16/2008 1:00 PM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: BERNIE ROCKERS Company: Phone: (785) 448-4816

Proposed Plugging Method: CLEAN OUT TO T.D. SET RETAINER AND PLUG SOLID WITH TUBING FROM TOTAL DEPTH TO SURFACE WITH CLASS A CEMENT. CUT CASING 4' BELOW SURFACE. BACKFILL AND RECLAIM SITE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/16/2008 4:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

LOGGING SHOWED THE POSSIBILITY OF CASING WEAKNESS AT SEVERAL LOCATIONS. THE CASING WAS PERFORATED FROM 489' TO 850' AND 887' TO 888' TO INSURE THE QUALITY OF THE PLUG JOB. 2" TUBING WAS RAN INTO THE WELL TO TOTAL DEPTH. CEMENT WAS PUMPED INTO THE 2" TUBING UNTIL CEMENT CIRCULATED FROM THE 6 5/8" CASING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. THE CASING WAS SHUT IN THE WELL WAS SQUEEZED AND SHUT IN.

RECEIVED  
KCC DISTRICT #3

JUL 23 2008 CPT

CHANUTE, KS

INVOICED  
DATE 8-18-08  
INV. NO. 2009060264

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 04 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

PPT