

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03469-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 26-11S-17W
1650 feet from S Section Line, 330 feet from W Section Line
Lease Name: HALL B Well #: 22
County: ELLIS Total Vertical Depth: 3500 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3500	0	w/150 sxs cmt
SURF	8.625	1155	0	w/550 sxs cmt <u>113.75</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/30/2008 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 600# hulls - 17 sxs gel spacer.
Prior squeeze jobs: 480' and 390' w/150 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/30/2008 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3382' - pumped 17 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1230' - pumped 150 sxs cement with 400# hulls - cwc.
PTOH. Topped 5 1/2" casing off with 25 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Hooked up to backside - instant 500#.

Perfs:

Top	Bot	Thru	Comments
3410	3416		

INVOICED
DATE 8-18-08
INV. NO. 2009060264

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 04 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

PKT

JUL 31 2008


CITIES SERVICE OIL CO. #22 HALL B 26-11-17W 34
 SW NW SW

Contr. _____ ELLIS County

E 1941 Comm. _____ Comp. 12-15-50 IP 32 BOPD

Tops	Depth	Datum	Casing
HEEB	3099	-1158	5" 3500 PERF 3476-82, 18 B0 & 75 BW/24 HRS: SQZ PERF 3465-71, 300' OIH/14 HRS: ACID 250 PMP 54 B0 & 7 BW/10 HRS
DODGE	3119	-1178	
LANS	3148	-1207	
ARB	3109	-1468	
T.D.	3500	-1559	

BEMIS-SHUTTS POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS