

TO  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 800 Bitting Building  
 Wichita, Kansas

File 83-38

Location Sec NW

Sec. 32 Twp. 28 Rge. 2E

I have today completed supervision of plugging of:

Well No. 1 (GAS) Lease Downs

Operator W. G. Talbott Address Brown Bldg., Wichita, Kansas.

Field Derby Gas County Sedgwick.

Total Depth 2232 Feet.

(Describe briefly the manner in which well was plugged)

Bottom of Hole cemented with 15 sacks of cement. (Cement placed in  
hole with "Dump Bailer") 8" casing ripped at 2020' and pulled. Hole  
filled with mud to 120'. Hole bridged at 120' with wood plug and rock  
and cemented with 15 sacks of cement. Hole filled to surface with  
heavy mud and capped with 5 sacks of cement. Cellar filled with  
soil.

Expense incurred as follows:

Date	Dec. 11, 1939	*Day	1/4	Mileage	40
	Dec. 14, 1939		1/4		38
Date	Dec. 15, 1939	*Day	1/4	Mileage	42
	Dec. 18, 1939		1/4		40
Date		*Day		Mileage	<del>160</del>

Hotel, meals, etc. \$ 4/4

\*Show as 1/4, 2/4, 3/4, or 4/4.

*F. D. Carter*

Conservation Agent  
 F. D. Carter

P. O. Wichita, Kansas. Date December 19, 1939.

**PLUGGING**  
 FILE 321282E  
 BOOK 83 LINE 38

