



TO  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 800 Bitting Building  
 Wichita, Kansas

File 55-42

Location SW-SW-NE

Sec. 32 Twp. 28 Rge. 2 E

I have today completed supervision of plugging of:

Well No. 1 Lease Schweitzer  
 Operator Dickey Oil Co. Address Ellis-Singleton Bldg., Wichita, Kansas  
 Field Downs County Sedgwick  
 Total Depth 2604 Feet.

(Describe briefly the manner in which well was plugged)

Filled with heavy mud from 2604 up to 2310; run wood plug and  
cemented up to 2200; Ripped pipe and pulled up four joints and filled  
with heavy mud; pulled pipe and filled with heavy mud to 1008 and run  
wood plug and cemented with 20 sacks cement; pulled surface pipe and  
filled to bottom of cellar and put cement cap in bottom of cellar.

( DRY HOLE )

Expense incurred as follows:

Date <u>March 27, 1939</u>	*Day <u>2/4</u>	Mileage <u>49 (two trips)</u>
<u>March 28, 1939</u>	<u>2/4</u>	<u>56 (two trips)</u>
Date <u>March 30, 1939</u>	*Day <u>1/4</u>	Mileage <u>26 (one trip)</u>
<u>March 31, 1939</u>	<u>1/4</u>	<u>60 (two trips)</u>

Hotel, meals, etc. \$ 11/2

\*Show as 1/4, 2/4, 3/4, or 4/4.

J. D. Carter  
 Conservation Agent

P. O. \_\_\_\_\_ Date \_\_\_\_\_

**PLUGGING**  
 FILE SEC 32 T 28 R 2 E  
 BOOK PAGE 55 LINE 42