

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SW SE SW

SEC. 31 TWP. 28 RGE. 2E

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Wheeler

Operator George P. Vye Address 1005 Central Bldg., Wichita, Kansas

Field _____ County Sedgwick

Total Depth 3171 Feet.

Plugging Contractor Capitt Drilling, Inc.,

Plugging Contractor's License No. Rotary drilled dry hole

Address 1005 Central Building, Wichita, Kansas
(Describe briefly the manner in which the well was plugged)

Filled hole with heavy drilling mud from total
depth to 140 feet. Set plug and cemented with
20 sacks of cement. Filled hole with extra heavy drilling
mud from 140' to 40'. Set plug and cemented with
10 sacks cement from 40' to 3'. Steel plate welded
on surface pipe.

*Zeid
5-25-55*

J.P. Roberts
District Conservation Agent

DATE May 22, 1955

PLUGGING
FILE SEC 31 T 28 R 2E
BOOK PAGE 121 LINE 8