

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION CE/2 NE NE

SEC. 26 TWP. 28S RGE. 2E

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Trustee

Operator J. P. Gaty Address 511 1/2 N. Hillside, Wichita, Kansas

Field _____ County Sedgwick

Total Depth 3350 Feet.

Plugging Contractor Martin Drilling Company

Plugging Contractor's License No. _____

Address Arkansas City, Kansas
(Describe briefly the manner in which the well was plugged)

132 feet of 8-5/8" surface pipe circulated with 90
sx cement. Filled hole full of heavy rotary mud to
150 feet. Set Halliburton plug and 20 sacks of cement
at 150 feet. Filled hole with mud to 30 feet of surface,
set second halliburton plug and 10 sacks of cement filling
hole with cement to base of cellar.

S. S. Greider
District Conservation Agent

DATE June 3, 1955

PLUGGING
FILE SEC 26 T 28 R 2E
BOOK PAGE 124 LINE 14