

R  
R

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 26 1966  
8-26-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Gom-Kat, Inc.

Complete Address: 1127 Wichita Plaza - Wichita, Kans.

Lease Name Ricks Well No. 1

Location SE-SW-NE- Sec. 16 Twp. 28 Rge. 2 (E) (W)

County Sedgewick Total Depth 3280

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kans. License No. 436

Operation Completed: Hour 11:45 Day 25 Month 8 Year 1966

The Above well was plugged as follows:

Pushed a plug in 5 1/2" casing to 2945 ft.  
Mixed & dumped 15 sacks Cement.  
Pulled 2896 ft. of 5 1/2" casing.  
Set a 20 ft. Rock Bridge at 180 ft.  
Added 6 cu. yds. of Redmix Cement to 50 ft.  
of surface: mudded hole to 25 ft. added  
10 ft. of Rock & 15 sacks of cement to surface.  
B.G.H.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-26-66 W. Ellinger

INV. NO. 4889-E

Signed: Paul Turpin  
Well Plugging Supervisor