

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01875-00-01
Spot: NWNWSE Sec/Twnshp/Rge: 22-10S-18W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SHEPARD I Well #: 2
County: ROOKS Total Vertical Depth: 3731 feet

Operator License No.: 33764
Op Name: INVESTMENT EQUIPMENT LLC
Address: 17509 COUNTY RD 14
FT MORGAN, CO 80701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3600	0	w/unknown sxs cmt
SURF	10.75	216	0	w/unknown sxs cmt

121-26

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/02/2008 8:00 AM
Plug Co. License No.: 34066 Plug Co. Name: TRINITY OILFIELD SERVICES INC.
Proposal Rcvd. from: BOB ALLEN Company: INVESTMENT EQUIPMENT LLC Phone: (405) 760-3682

Proposed	Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Plugging	Tagged fish with mill - milled 30'.
Method:	Drilled over fish with drill pipe - two joints (70'). Tried to wash over with nine joints. Tagged fish at 1180'. 2,420' of tubing left in the hole.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/02/2008 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at the base of the surface pipe.
Ran tubing to 1200' - pumped 150 sxs 60/40 pozmix - 4% gel with 500# hulls - circulated cement to pit.
Pulled all tubing.
Hooked onto 5 1/2" casing - pumped 25 sxs 60/40 pozmix - 4% gel.
S.I.P. 200#.

Perfs:

INVOICED
DATE 7-24-08
INV. NO. 2009060150

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 10 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #2442.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

JUL 08 2008

DAVIS BROTHERS #2 SHEPARD 22-10-18W
NW NW SE

Contr. TRANSIT CORP ROOKS County

E 2066RB Comm. Comp. IP 100 BOPD
O W W O

Tops	Depth	Datum
ANH	1405	+661
TOP	3037	-971
HEEB	3258	-1192
TOR	3276	-1210
LANS	3301	-1235
CONG	3551	-1485
SIMP	3668	-1602
ARB	3681	-1615
TD	3731	-1665

Casing ORIG COMP AS D & A BY
10" 216 LEE PHILLIPS 6-3-55
5" 3600
DST 3358-91/1 HR, 510' SW
NEW INFORMATION:
CO 3547: PERF 3508-11: 3527-29
ACID 500: 5.01 BFPH, 77% OIL/6
HRS: FU 2000' FIH, 75% OIL: SWB
7.68 BFPH/3 HRS, 70% OIL

EILERS POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

LEE PHILLIPS #1 SHEPARD 22-10-18W
NW NW SE

Contr. ISERN DRILLING ROOKS County

E 2066RB Comm. Comp. 6-3-55 IP D & A

Tops	Depth	Datum
ANH	1405	661
TOP	3037	-971
HEEB	3258	-1192
TOR	3276	-1210
LANS	3301	-1235
CONG	3551	-1485
SIMP	3668	-1602
ARB	3681	-1615
TD	3731	-1665

Casing 10" 216
DST 3358-91/1 HR, 510' SW

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS