

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20819-00-00
Spot: NENESE Sec/Twnshp/Rge: 10-18S-1E
2274 feet from S Section Line, 85 feet from E Section Line
Lease Name: W SCULLY Well #: 1-10
County: MARION Total Vertical Depth: 3265 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3205		
PROD	5.5	3271	1550	325
SURF	8.625	215		125

106.11

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/02/2008 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PBTD @ 3,205'. SAND TO 3,060 & TOP WITH 5 SXS. CEMENT. RIP 5 1/2" CASING & PULL TO 265'. CIRCULATE CEMENT FROM 265' TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 07/02/2008 2:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:
SANDED TO 3,050 & TOPPED WITH 5 WXS. CEMENT. RIPPED 5 1/2" CASING @ 1,550'. PULLED CASING TO 265' & CIRCULATED 120 SXS. CEMENT TO THE SURFACE.

Perfs:

Top	Bot	Thru	Comments
3254	3259		
3242	3246		
3216	3222		
3110	3111		

INVOICED

DATE 7-24-08
INV. NO. 2009060161

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 17 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY QUALITY OIL WELL CEMENTING, INC. INVOICE #1861.
Plugged through: CSG

District: 02 Signed Michael Wilson
(TECHNICIAN)