

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-06412-00-00  
Spot: E2NENE Sec/Twnshp/Rge: 12-11S-18W  
4620 feet from S Section Line, 330 feet from E Section Line  
Lease Name: RIDLER A-EAST Well #: 2  
County: ELLIS Total Vertical Depth: 3444 feet

Operator License No.: 30537  
Op Name: VENTURE RESOURCES, INC.  
Address: PO BOX 101234  
DENVER, CO 80250

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3605	0	w/unknown sxs cmt
PROD	5.5	3442	0	w/unknown sxs cmt <u>111.93</u>
SURF	8.625	1176	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/08/2008 3:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOHN COARLEY Company: VENTURE RESOURCES, INC. Phone: (785) 731-5073

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 17 sxs gel spacer. CIBP 3438'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/08/2008 6:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2580'. Swift Services pumped 17 sxs gel spacer, followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1178'. Swift Services pumped 170 sxs 60/40 pozmix with 300# hulls - cwc. PTOH. Topped 5 1/2" off with 35 sxs cement - casing full.  
Hooked up to 8 5/8" - instant 500#.

Perfs:

Top	Bot	Thru	Comments
3431	3435		

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 11 2008

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 7-24-08  
INV. NO. 2009 060162

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams  
(TECHNICIAN)

CM

Form CP-2/3

JUL 09 2008