

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21222-00-00
Spot: SWSESW Sec/Twnshp/Rge: 30-15S-10W
480 feet from S Section Line, 1700 feet from W Section Line
Lease Name: CHARVAT Well #: 4
County: ELLSWORTH Total Vertical Depth: 3320 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	361		

107.90

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/14/2008 10:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: JAY KRIER Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-4477

Proposed Plugging Method: FILL HOLE WITH HEAVY MUD & SPOT CEMENT THROUGH DRILL PIPE. SPOT 35 SKS. CEMENT @ TOP OF ARBUCKLE, 35 SKS. CEMENT @ 1,325', 35 SKS. CEMENT @ 1,050', 35 SXS. CEMENT @ 410', 25 SKS. CEMENT @ 60', AND 15 SKS. CEMENT IN RAT HOLE.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: NONE
Date/Time Plugging Completed: 07/14/2008 1:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

FILLED HOLE WITH HEAVY MUD & SPOTTED CEMENT THROUGH DRILL PIPE.
SPOTTED 35 SKS. CEMENT @ 3,264', 35 SKS. CEMENT @ 1,325', 35 SKS. CEMENT @ 410', 25 SKS. CEMENT @ 60', AND 15 SKS. CEMENT IN RAT HOLE.

Perfs:

INVOICED
DATE 7-28-08
INV. NO. 2009060106

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 17 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING CO., LLC. INVOICE #42779.

Plugged through: DP

District: 02

Signed

Michael Wilson
(TECHNICIAN)

PKT