

2 030466

217 R

API NUMBER 15-173-20,550-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SE, SEC. 30, T 28 S, R 2 #1E

TECHNICIAN'S PLUGGING REPORT

Operator License # 8169

2310 feet from S section line

330 feet from E section line

Lease Name Anderson Well # 1

County Sedgwick 73.91

Well Total Depth 2274' feet

Conductor Pipe: Size 4 1/2" feet 2245'

Surface Casing: Size 8 5/8" feet 211'

Operator: Avanti Petroleum Inc.

Name & Address 300 W. 79st. South

Wichita, Ks. 67233

Lease Owner Beech Aircraft Corporation

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Lewis Long License Number 6443

Address Hamilton, Ks.

Company to plug at: Hour: 12:00 Day: 17 Month: 9 Year: 19 86

Plugging proposal received from Robert J. Gaut

(company name) consultant Beech Aircraft Corporation (phone) 405-942-1951

were: fill hole / mud. spot cent. 2025' to total depth, rip and pull 4 1/2" csg. to 300' pump cent. down 4 1/2" circ cent. to surface, pull 4 1/2" csg. fill hole with cement.

Plugging Proposal Received by Nist #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 13:15 Day: 19 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT ran tub 2272', filled hole with heavy mud

Halliburton Services #352103-4 spotted, 30 cu C.A. cent, pulled tub to 1700', circ tub clean, ran tub top of cent. 2000'

Ripped and pulled 1840' 4 1/2" csg. Halliburton pumped 130 cu C.A. cent. down 4 1/2" from 320' to surface, pulled 4 1/2" csg. filled hole with cement.

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

Remarks: Billed to Beech Aircraft Corp. Att. Mr. J. E. Beckett.
(If additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

DATE 10-9-86

INV. NO. 15130

Signed Alan Thompson 10-6-86
(TECHNICIAN) OCT 6 1986