

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20,610-00-00

NE SWSW, SEC. 29, T 28 S, R 2 W 1/2 E

990 FEET FROM N SECTION LINE

990 FEET FROM W SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5152

LEASE NAME PLAVCAN WELL # 1-29

OPERATOR: BANKS OIL CO
NAME & ADDRESS: 200 W DOUGLAS
Ste. 550
Wichita, KS

COUNTY Sedgwick

WELL TOTAL DEPTH 2320 FEET

CONDUCTOR PIPE: SIZE - FEET -

SURFACE CASING: SIZE 8 5/8 FEET 205

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR EDCO DRILL LICENSE NUMBER 5676

ADDRESS 114 W. LOCUST EL DORADO KS

COMPANY TO PLUG AT: HOUR: _____ DAY: 21 MONTH: 11 YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM RON GULICK

(COMPANY NAME) ABOVE (PHONE) _____

WERE: 35' x 2' @ 1100'

35' x 2' @ 260'

25' x 1' ON W-R. Plug @ 60'

10' x 1' R.H.

PLUGGING PROPOSAL RECEIVED BY Ron Wilson
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 8:25 AM DAY: 21 MONTH: 11 YEAR: 19 83

ACTUAL PLUGGING REPORT RAN DRILL PIPE TO 1100' & SURF OF WYPT (PERMITS)
SPOTTED 35' x 2' COM. CONC. CLEARED HOLE WITH 5 BARRELS WATER &
DISPLACED WITH DRILL MUD. PULLED PIPE TO 260' & SPOTTED 35' x 2'
CON. PULLED D.R. & PUSHED W-R. PLUG TO 60' FLUSHED WITH FRESH
WATER & CIRCULATED 25' x 1' CON TO SURFACE. THRU DRILL PIPE
CIRC. 10' x 1' IN RAT. HOLE

REMARKS: Ticket # 5618

I (DID 1 DID NOT) OBSERVE THIS PLUGGING.

SIGNED Ron Wilson
(TECHNICIAN)

INVOICED
DATE 12-16-83
INV. NO. 5108-F

RECEIVED
STATE CORPORATION COMMISSION

FORM CP-213
REV. 6-83

NOV 28 1983
11-28-83
CONSERVATION DIVISION