

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-173-20281-00-00  
Spot: S2SESW Sec/Twnshp/Rge: 8-26S-2E  
330 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: TJADEN B Well Number: 7  
County: SEDGWICK Total Vertical Depth: 3493 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 200 160 SX CMT  
Production: Size 4.5 feet: 3490 160 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_ 9113.52

Well Type: EOR UIC Docket No: E24832.1 Date/Time to Plug: 07/10/2001 9:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.  
Proposal Rcvd. from: DICK SCHREMMER Company: GRESSEL OILFIELD SERVICE, INC Phone: (316) 524-1225

Proposed Plugging Method: Sand to 3,310' and top with 4 sxs. cement. Shoot pipe off and pull same. Run tubing to 250' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 07/10/2001 12:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,280' and topped with 4 sxs. cement. Shot pipe off 2,028' and pulled same. Ran tubing to 255' and circulated 75 sxs. cement to the surface. On 07/11/01 topped with 20 sxs. cement. Perforations from 3,360' to 3,372'.

RECEIVED  
KCC DISTRICT #2

INVOICED  
DATE 7-12-01  
INV. NO. 2002060047

JUL 12 2001  
7-12-01  
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENTING. INVOICE #20776.

Plugged through: TBG

District: 02

Signed Michael Wilson  
(TECHNICIAN)