

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21632-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 6-31S-7W
1650 feet from N Section Line, 330 feet from W Section Line
Lease Name: LECHNER A Well #: 3
County: HARPER Total Vertical Depth: 4401 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	268		

143.03

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/29/2008 8:00 PM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING Phone: (620) 786-7133

Proposed Plugging Method: 35 SKS 1350, 35 SKS 900, 35 SKS 318, 25 SKS 60', 15 SKS RH, 10 MH

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 07/29/2008 10:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE DRILL PIPE WAS RUN IN THE WELLBORE TO 1350', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 900', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 318', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 60', WHERE 25 SKS OF CMT WAS CIRCD TO SURFACE. THE RATHOLE WAS CIRCD WITH 15 SKS OF CMT. THE MOUSE HOLE WAS CIRCD WITH 10 SKS OF CMT.

Perfs:

INVOICED
DATE 8-18-08
INV. NO. 2009060239

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 06 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CMTG 31282 60/40 4% GEL

Plugged through: DP

District: 02

Signed [Signature]
(TECHNICIAN)

PKT