

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Hupfer Operating, Inc.
Address: P.O. Box 216
Phone: (785) 628-8666 Operator License #: 30380
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15 - 159-22405-0000
Lease Name: Bayer
Well Number: 1
Spot Location (QQQQ): N/2 - NW - SE - SE
1170 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 31 Twp. 19 S. R. 10 East West
County: Rice
Date Well Completed: _____

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

Plugging Commenced: 7-22-08
Plugging Completed: 7-23-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	238'	None
				5-1/2"	3292.5	1990'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3060' and 5 sxs. cement. Set CIBP @2750' with 2 sxs. cement on top. Cut casing loose @1990', pulled up to 1317', pumped 35sxs. cement, pulled up to 900', pumped 35 sxs. cement, pulled up to 288' and circulated 100 sxs. cement to surface, 6/40 pos, 4% gel.
Layed down rest of casing. Topped off with 25 sxs. cement. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 20 2008
CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Hupfer Operating, Inc.
State of Kansas County, Rice, ss.

Mike Kelos (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 18th day of August, 20 08

[Handwritten Signature]
Notary Public

My Commission Expires: _____

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202