

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sedgwick County. Sec. 8 Twp. 26S Rge. 2 (E) (W)
Location as "NE/CNW%SW%" or footage from lines Sen. S/2 SW/4 NW/4

Lease Owner John P. Gaty

Lease Name Timmerkamp Well No. 4

Office Address 11 Cypress Dr., Wichita 8, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Nov. 1 1952

Application for plugging filed Nov. 3 1952

Application for plugging approved Nov. 4 1952

Plugging commenced Nov. 5 1952

Plugging completed Nov. 5 1952

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well D. C. Lilley

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2991 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 140'
15' rock bridge W/10 sacks cement 140' to 125'
Mud to 20'
10' rock bridge W/5 sacks cement 20' to 10'
Mud to surface

RECEIVED
STATE CORPORATION COMMISSION
NOV 11 1952
11-11-52
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Company Tools
Address _____

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Wm. Vallandigham (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wm. Vallandigham
547 N. Green, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of November, 1952
J. Arnold Sawd
Notary Public.
My commission expires December 12, 1955

PLUGGING
FILE SEC 8 T 26 R 25
BOOK PAGE 56 LINE 35



WELL LOG - Timerkamp #4

OPERATOR: Mr. J. P. Gaty
c/o Beech Aircraft Corp.
Wichita, Kansas

LOCATION: SE SW NW
Section 8-26-2E
Sedgwick County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.
P. O. Drawer 712
El Dorado, Kansas

PRODUCTION: D. & A.

Farm: Timerkamp Well No. 4

Date Commenced: October 24, 1952
Date Completed: October 29, 1952

Total Depth: 2966½ feet - Rotary

<u>From</u>	<u>To</u>	<u>Formation</u>	<u>Cable Tool Log</u>	
30	75	Cement	2966½-2986	Sandy Shale
75	250	Shells & Shale brks.	2986-2991	Miss. Lime
250	485	Shale & Lime	2991	Total Depth
485	610	Lime & Shale strks.		
610	615	Red Bed		
615	845	Lime & Shale		
845	980	Shale		
980	1080	Shale & Lime		
1080	1415	Shale		
1415	1455	Shale & Lime shells		
1455	1730	Shale & Lime strks.		
1730	2115	Shale & Lime		
2115	2135	Shale		
2135	2200	Lime		
2200	2300	Shale & Lime strks.		
2300	2480	Lime & Shale		
2480	2530	Shale		
2530	2605	Lime & Shale		
2605	2686	Lime & Shale strks.		
2686	2705	Lime & Shale		
2705	2822	Shells & Shale		
2822	2919	Shale & Lime strks.		
2919	2937	Shale & Sand		
2937	2966½	Shale & Shells		
2966½		Total Depth.		

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Timerkamp #4 well drilled for Mr. J. P. Gaty and completed October 29, 1952.

MORRISON DRILLING COMPANY, INC.

C. W. Wilson - Secretary-Treasurer

STATE OF KANSAS)
) ss.
COUNTY OF BUTLER)

SUBSCRIBED AND SWORN TO, Before the Undersigned, a Notary Public, in and for the County and State aforesaid this 29th day of October, 1952.

Notary Public

My Commission Expires January 10, 1955.

PLUGGING
FILE SEC 87-26R-2E
BOOK PAGE 56 LINE 35

STATE CORPORATION COMMISSION
NOV 20 1952
CONSERVATION DIVISION
Wichita, Kansas