

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Sedgwick County, Sec. 8 Twp. 26 Rge. 2 (E) E (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Tom-Kat, Inc.

Lease Name Schramm "A" Well No. 3

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 10-21-65 19

Plugging completed 10-23-65 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Paul Turpin

Producing formation Depth to top Bottom Total Depth of Well 3013 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	135'	None
				5-1/2"	3013'	2692'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3013', sanded hole to 2980' and dumped 5 sacks of cement @ 2980' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 180' to 165' and dumped 20 sacks of cement @ 165'. Mudded hole to 35', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
10-28-65  
OCT 28 1965

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1965

Milton J. Volin

Notary Public.

My commission expires May 20, 1968

Tomp-Kat, Inc.

8-26-2E

COPY


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 E. Murdock, Wichita, Kansas

Company - RIPSTRA-TURNER COMPANY  
Farm - Schram "A" No. 3

SEC. 8 T. 26 R. 2E  
NE NE SW

Total Depth. 3013  
Comm. 5-14-50 Comp. 5-24-50  
Shot or Treated.  
Contractor. Eckland Drilling Co.  
Issued. 7-29-50

County. Sedgwick  
KANSAS



CASING:  
8 5/8" 92' cem w/50 sx.  
5" 2992'

Elevation. 1144 R.B.

Production. 176 bbls

Figures indicate Bottom of Formations.

surface clay	38
shale, shells	150
lime, shale	235
anhydrite	250
lime, shale	795
shale, shells	1310
lime shale	2360
lime	2380
lime, shale	2540
lime	2705
lime, shale	2993
sand RTD	2994
sand	3013
Total depth	

Tops: Corr. to Barrick Floor  
Kansas City 2533  
Burgess Sand 2992

Filled hole with sand 3002-3013'

Perforated Burgess Sand 2997-1553 (Top Oil)  
3002-1558

No shows

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 14 1965  
OBSERVATION DIV.  
KANSAS