

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Sedgwick SEC. 8 TWP 26S RGE. 2E E/W  
Location as in quarters or footage from lines:  
30' E of SW SE NW/4


Lease Owner Wiley R. Ash  
Lease Name Kraus #1 Well No. \_\_\_\_\_  
Office Address RR #1, Box 114, Rose Hills, Ks. 67133  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 3/10/81  
Plugging completed 3/12/81  
Reason for abandonment of well or producing formation Depleted

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3511'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	203'	None
				4-1/2"	3004'	2387'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in. Raised mast, dug cellar and plugged off bottom. Pushed plug to 2990' and ran sand and 4 sacks cement. 18" stretch. Made shot at 2400 and worked pipe loose. Pulled total string of 60 joints. Set rock bridge at 215' and ran 5 yards ready mix cement. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of March, 1981

My Commission expires:



Joan Kelso  
Notary Public.  
RECEIVED  
CORPORATION COMMISSION  
MAR 18 1981  
3-18-81  
CONSERVATION DIVISION  
Wichita, Kansas

# Petro-Log

# Radiation Guard Log

COMPANY Wiley Ash, SR.

WELL KRAUS #1

FIELD Fairview

COUNTY Sedgwick STATE KANSAS

Location 30' E. of SW-SE-NW/4

Other Services:

Section 4 Twp. 26s Rge. 2E

Permanent Datum: G.L. Elev.: 1437  
 Log Measured From K.B. 5.0 Ft. Above Perm. Datum  
 Drilling Measured From K.B.

Elev.: K.B. 1442  
 D.F. 1440  
 G.L. 1437

Date	<u>3-26-79</u>					
Run No.	<u>0NG</u>					
Depth—Driller	<u>3511</u>					
Depth—Logger	<u>3507</u>					
Btm. Log Inter.	<u>3506</u>					
Top Log Inter.	<u>0</u>					
Casing—Driller	<u>8 5/8</u>	<u>@ 203</u>	<u>@</u>	<u>@</u>	<u>@</u>	<u>@</u>
Casing—Logger						
Bit Size	<u>7 7/8</u>					
Type Fluid in Hole	<u>CHEMICAL</u>					
Dens.	Visc.	<u>9.5</u>	<u>51</u>			
pH	Fluid Loss	<u>11.0</u>	<u>9.6</u> ml	ml	ml	ml
Source of Sample	<u>Flowline</u>					
R <sub>m</sub> @ Meas. Temp.	<u>1.2</u>	<u>@ 62°F</u>	<u>@</u>	<u>°F</u>	<u>@</u>	<u>°F</u>
R <sub>m</sub> @ Meas. Temp.	<u>9</u>	<u>@ 62°F</u>	<u>@</u>	<u>°F</u>	<u>@</u>	<u>°F</u>
R <sub>oo</sub> @ Meas. Temp.	<u>1.8</u>	<u>@ 62°F</u>	<u>@</u>	<u>°F</u>	<u>@</u>	<u>°F</u>
Source: R <sub>m</sub>	R <sub>oo</sub>	<u>CHARTS</u>				
R <sub>m</sub> @ BHT	<u>.66</u>	<u>@ 112°F</u>	<u>@</u>	<u>°F</u>	<u>@</u>	<u>°F</u>
Time Since Circ.	<u>3 1/2 HRS.</u>					
Max. Rec. Temp.	<u>112</u>			<u>°F</u>	<u>°F</u>	<u>°F</u>
Equip.   Location	<u>H-3   @ wichita</u>					
Recorded By	<u>GASKILL</u>					
Witnessed By	<u>MR. L. E. CARTER &amp; MR. ASH</u>					