

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

LICENSE # 8169 EXPIRATION DATE 6-30-83  
 OPERATOR AVANTI PETROLEUM, INC. API NO. 15-173-20,550-00-00

ADDRESS 330 West 79th St. South COUNTY Sedgwick  
Wichita, Kansas 67233 FIELD Derby

\*\*CONTACT PERSON Ed Miller LEASE Anderson  
 PHONE 316/685-7293 PROD. FORMATION Stalnaker

PURCHASER Shut-in no purchaser at this time. WELL NO. 1  
 ADDRESS \_\_\_\_\_ WELL LOCATION NE NE SE

DRILLING CONTRACTOR DUKE DRILLING CO., INC. the SE/4 SEC. 30 TWP. 28S RGE. 2E  
 ADDRESS P. O. Box 823  
Great Bend, Kansas 67530


PLUGGING CONTRACTOR none

ADDRESS \_\_\_\_\_  
 TOTAL DEPTH 2245+29' open hole PBTD \_\_\_\_\_

SPUD DATE 1-18-83 DATE COMPLETED 1-22-83

ELEV: GR 1362DF KB

DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(CABLE)~~ TOOLS (New)/(Used) casing.  
 Report of all strings set — surface, intermediate, production, etc. ~~XXXXX~~



WELL PLAT (Quarter) \_\_\_\_\_ Section - Please indicate.

KCC   
 KGS   
 MISC. \_\_\_\_\_

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Pipe	12 1/2"	8 5/8"	21 lb.	211	Common	75	3% calcium chlori
Production Casing	7 7/8"	4 1/2"	14 lb.	2245	Common	150	3% calcium chlori

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
none					

TUBING RECORD				
Size	Setting depth	Packer set at		
2 3/8"	2240	none	open-hole	2245-2274

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
None	

RECEIVED  
 STATE CORPORATION COMMISSION  
 9-15-83  
 SEP 15 1983

TEST DATE: <u>February 2, 1983</u>	PRODUCTION	CONSERVATION DIVISION Wichita, Kansas
Date of first production	Producing method (flowing, pumping, gas lift, etc.) <u>Flowing Gas Well</u>	A.P.I. Gravity
RATE OF PRODUCTION PER 24 HOURS	Oil <u>None</u> bbls. Gas <u>8,800</u> MCF Water <u>0 %</u> no bbls. Gas-oil ratio <u>All Gas</u> CFPB	
Disposition of gas (vented, used on lease or sold) <u>For Sale</u>	Producing interval(s) <u>2245-2265</u>	

\*\* The person who can be reached by phone regarding any questions concerning this information.  
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum Wellington Depth 90'  
 Estimated height of cement behind pipe 211'

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale	-645		Heebner	2005
Limestone	-881		Iatan	2241
Sandstone TSTD 8,800,000 CFPD	-893		Stalnaker	2253

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

**AFFIDAVIT**

STATE OF Kansas, COUNTY OF Sedgwick SS,


Edward E. Miller OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS President FOR Avanti Petroleum, Inc.  
 OPERATOR OF THE Anderson LEASE, AND IS DULY AUTHORIZED TO MAKE THIS  
 AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON SAID LEASE HAS  
 BEEN COMPLETED AS OF THE 9th DAY OF August 19 83, AND THAT ALL  
 INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT, SAITH NOT.

(S) Edward E. Miller

SUBSCRIBED AND SWORN TO BEFORE ME THIS 13th DAY OF September 19 83



Catherine E. Martzall  
 NOTARY PUBLIC  
 Catherine E. Martzall

MY COMMISSION EXPIRES: July 15, 1985