

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warroir inc.

Address: P.o. Box 399 Garden City Ks. 67846

Phone: (620) 272-1023 Operator License #: 4058

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8/14/08 (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Table with 4 columns: Formation Name, Depth to Top, Bottom, T.D. Rows include Topeka and Lansing.

API Number: 15-159-02010-00-00

Lease Name: Buehler

Well Number: #2

Spot Location (QQQQ): Cher - NW - NW - NW

330' Feet from North / South Section Line

330' Feet from East / West Section Line

Sec. 330 Twp. 18 S. R. 10 East West

County: Rice

Date Well Completed: 8/16/49

Plugging Commenced: 8/15/08

Plugging Completed: 8/15/08

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out).

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Perf 1250',900', 525', 4spf. Run tbg to 2400'. Sand back to 2494'. Spotted 10sx 60/40 pos,4%gel on top of sand. Pulled tbg to 1278' spotted 35sx 60/40 pos,4% gel. Pulled tbg to 943' spotted 35sx 60/40,4% gel. Pulled tbg to 580' pumped 210sx 60/40 pos 4% gel Cement circulated to surface. Pulled tbg. Topped 51/2 off with 25 sx. Dumped 1sx portland cement down 51/2. Cut casing off 6' below ground and back fill.


Name of Plugging Contractor: Swift Services Inc. License #: 32382

Address: P.O. Box 466 Nesscity Ks. 67560

Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Kansas County, Finney, ss.

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]

(Address) P.O. Box 399 Garden City Ks. 67846

SUBSCRIBED and SWORN TO before me this 19 day of August 20 08

[Handwritten Signature] My Commission Expires: 09-12-09