




WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail of Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Sedgwick County. Sec. 25 Twp. 26S Rge. 2 (E) X (W)  
Location as "NE/CNW&SW" or footage from lines SW SW SW  
Lease Owner Brady Lowe, et al  
Lease Name Sloan Well No. 1  
Office Address 1512 Gt. Plains Life Bldg, Lubbock, Texas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 10, 19 64  
Application for plugging filed March 10, 19 64  
Application for plugging approved March 10, 19 64  
Plugging commenced March 10, 19 64  
Plugging completed March 10, 19 64  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3328 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole with 42 Viscosity Mud to 197 feet. Set dry hole plug. Added 1/4 sack hulls and 20 sacks cement. Mudded hole from this point to 30 feet. Set a plug. Added 1/4 sacks hulls and 8 sacks cement. Capped rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 13 1964

3-13-64

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Canaday Drilling Co.  
Address 6427 East Kellogg, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Kelly Baze (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. R. Baze  
1512 Gt. Plains Life Bldg, Lubbock, Texas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of March, 19 64

Laura S. Matt  
Notary Public.



WELL LOG

COMPANY: Brady Lowe, et al  
1512 Gt. Plains Life Bldg.  
Lubbock, Texas

COMMENCED: March 2, 1964  
COMPLETED: March 10, 1964

LEASE: Sloan #1  
LOCATION: SW SW SW 25-26S-2E  
Sedgwick, County, Kansas

TOTAL DEPTH: 3328  
ELEVATION: 1365 KB

CONTRACTOR: Canaday Drilling Company  
6427 East Kellogg  
Wichita, Kansas

CASING: 151 feet of 8 5/8 inch with 145 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

APR 9 1964

FIGURES INDICATE BOTTOM OF FORMATION

CONSERVATION DIVISION  
Wichita, Kansas

148	Shale	2515	Lime
335	Lime	2640	Lime
640	Lime - Shale	2760	Shale and Lime
1006	Shale and Shells	2878	Shale w/ Lime
1375	Shale w/ Lime St.	3140	Lime
2155	Shale and Lime	3195	Shale
2279	Lime - Shale	3258	Lime - Shale
2321	Lime	3320	Shale and Lime
2365	Shale	3328	Lime
2420	Shale w/ Lime		

I, Granville E. Canaday, of the  
CANADAY DRILLING COMPANY certify  
the above Well Log to be true to the  
best of my knowledge.

Granville E. Canaday  
Granville E. Canaday

Subscribed and sworn to before me, a Notary Public in and for Sedgwick County,  
Kansas this 11th day of March, 1964.

Laura S. Matt

*Notary Public - expires February 5, 1968.*