


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sedgwick County, Sec. 26 Twp. 26S Rge. 2E (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner O. A. Sutton
Lease Name Wilson Well No. 1
Office Address 407 Ins. Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Nov. 15 1960
Application for plugging filed Nov. 15 1960
Application for plugging approved Nov. 15 1960
Plugging commenced Nov. 15 1960
Plugging completed Nov. 15 1960
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lee Guthrie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3345' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	210'	


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud from 3345 to 180'. Set plug #1 with 1/4 sack hulls and 15 sacks cement. Filled with mud up to 25'. Set plug #2 with 1/4 sack hulls and 10 sacks cement. Put 2 sacks of cement in rat hole. Plugged at 12:30 a.m. November 15, 1960

RECEIVED
STATE CORPORATION COMMISSION
11-23-60
NOV 23
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. S. Sutton Drilling Co.
Address 313 Ins. Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
D. G. Comstock (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) D. G. Comstock
407 Ins. Bldg., Wichita, Kansas
(Address)
SUBSCRIBED AND SWORN to before me this 16th day of November, 1960
Sara Wimberly
Notary Public.

My commission expires Feb. 5, 1964

Wilson #1 - O. A. Sutton
SW SW NE Section 26-26S-2E
Sedgwick County, Kansas

Date Commenced - November 2, 1960
Date Completed - November 15, 1960
Elevation - 1383 K.B.
Casing - 210' of 10-3/4" with 175 sacks of HA5 Cement.
Total Depth - 3345'

DRILLERS LOG FOR WILSON #1

0 - 210	
210 - 365	Lime and Shale
365 - 660	Lime and Shale
660 - 980	Lime and Shale
980 - 1370	Shale and Lime
1370 - 1670	Shale and Lime
1670 - 1835	Shale and Lime
1835 - 2076	Lime and Shale
2076 - 2250	Lime and Shale
2250 - 2395	Lime and Shale
2395 - 2505	Lime and Shale
2505 - 2583	K.C.
2583 - 2677	Lime and Shale
2677 - 2767	Lime
2767 - 2855	Lime
2855 - 2884	Shale
2884 - 2923	Miss/Lime
2923 - 2984	Miss
2984 - 3016	Miss (Chat)
3016 - 3046	Miss (Churty Lime)
3046 - 3070	Miss
3070 - 3113	Lime and Miss
3113 - 3142	Miss and Lime
3142 - 3158	Miss and Lime
3158 - 3191	Kinderhook Shl.
3191 - 3201	--
3201 - 3305	Lime
3205 - 3253	Lime
3253 - 3263	Lime and Sand
3263 - 3294	Simpson
3294 - 3310	Simpson
3310 - 3326	Shale
3326 - 3339	Arbuckle
3339 - 3345	D & A

RECEIVED
NOV 23 1960

SEVEN DIVISION
Wichita, Kansas

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true to the best of my knowledge and belief and according to the records of this office.

J. S. SUTTON DRILLING COMPANY

By James J. Sutton, Jr.

Subscribed and sworn to before me this 22nd day of November 1960.

Harry S. Fickler
Notary Public

My Commission expires February 27, 1961.