


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Sedgwick County, Sec. 26 Twp. 26S Rge. 2 (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NE
Lease Owner D. G. Hamilton et al
Lease Name Wilson Well No. 1
Office Address 223 Beacon Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 23, 1955 19
Application for plugging filed September 23, 1955 19
Application for plugging approved September 23, 1955 19
Plugging commenced September 23, 1955 19
Plugging completed September 23, 1955 19
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well S. S. Greider
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2911 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	107'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

107 feet of 8-5/8" surface pipe circulated with cement
Bottom of hole circulated with heavy rotary mud up to
100 feet. Set plug and 15 sacks of cement thru the
drill pipe. Mudded hole to 30 feet of surface; set plug
and ten sacks of cement to base of cellar.

RECEIVED

STATE CORPORATION COMMISSION
9-23-55
SEP 23 1955

Name of Plugging Contractor L. C. Smitherman
Address Box 627, Augusta, Kansas

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) D. G. Hamilton

223 Beacon Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23 day of September, 1955

My commission expires Jan. 31, 1957

Seward S. Greider
Notary Public.



PLUGGING
FILE SEC 26 T 26 R 2E
BOOK PAGE 2 LINE 29

WILSON #1

Company - D. G. Hamilton
Contractor - L. C. Smitherman Drlg. Co.

Location: NW NW NE, Section 26-26S-2E,
Sedgwick County, Kansas
Elevation: 1395'
Casing: 8 5/8 - 100' cemented W/ 75Sk.

Commenced - 9-15-55
Completed - 9-22-55
Rotary Total Depth - 2911
Initial Production - D. & A.

Figures Indicate Bottoms of Formations:

Depth	Formation
107 - 195	Shale & Shells
195 - 395	Shale W/lime Strks.
395 - 690	Lime W/Shale Strks.
690 - 870	Shale & Shells
870 - 1135	Shale & Lime
1135 - 1180	Shale
1180 - 1302	Lime
1302 - 1390	Shale & Lime
1390 - 1485	Lime W/Shale Strks.
1485 - 1663	Lime & Shale
1663 - 1711	Lime
1711 - 1805	Shale & Lime
1805 - 1935	Lime & Shale Strks.
1935 - 2090	Lime & Shale
2090 - 2190	Lime
2190 - 2315	Lime & Shale Strks.
2315 - 2433	Shale & Lime
2433 - 2446	Shale
2446 - 2608	Lime - K. C.
2608 - 2679	Lime & Shale
2679 - 2835	Lime W/Shale Strks.
2835 - 2909	Lime & Shale
2909 - 2911	Chat
2911 - R. T. D.	

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Wilson #1, located in the NW NW NE, Section 26-26S-2E, Sedgwick, County, Kansas.

L. C. SMITHERMAN DRILLING COMPANY

Joe W. Cain
Joe Cain - Superintendent

Subscribed and sworn to before me this 26th day of September, 1955.

Lute H. Carter
Notary Public

My commission expires October 23, 1958.

RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 26 T 26 R 2E
BOOK PAGE 2 LINE 29