

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sedgwick County. Sec. 27 Twp. 26 Rge. 2E (E) (W)
SW 1/4 NE 1/4 NW 1/4

NORTH



Locate well correctly on above Section Plat

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines
Lease Owner J. P. Gaty
Lease Name E. G. Harpstrite Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 3-26 19.46
Application for plugging filed 3-26 19.46
Application for plugging approved 3-26 19.46
Plugging commenced 3-27 19.46
Plugging completed 3-30 19.46
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. L. Loman
Producing formation None Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				7"	2920	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud to 180 feet. Put in 12 foot rock bridge and cemented with fifteen sacks of cement. Filled with mud to 15 feet. Put in ten foot rock bridge and cemented with five sacks of cement. Filled to surface.

PLUGGING
FILE SEC 27 26 2E
BOOK PAGE 47 LINE 40



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J. P. Gaty
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
B. V. Cox (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B V Cox

El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of April, 1946

My commission expires May 14-1949

Notary Public

COMPANY: J. P. Gaty
FARM: Harpestrite No. 2

Sec. 27 Twp. 26 Rge. 2E
SW NE NW

Total Depth: 2960
Comm. 11-28-45 Comp. 1-25-46
Shot or treated:
Contractor:

Casing: 13 1/4" 134'
7" 2920

Elevation: 1403
Production: Dry

Figures below indicate bottom of formation

clay & shale	0-100	chert or chat various	
lime	222	colored shale	2940
lime shale & sand	355	chert or chat various	
sandy lime	475	colored shale	2941
shale	530	chert or chat various	
lime	685	colored shale	2944
shale & lime	1125	chert or chat various	
shale-lime shell	1285	colored shale	2946
shale & lime	1485	chert or chat various	
lime & shale	1635	colored shale	2950
lime	1810	chert or chat various	
shale	1840	colored shale	2953
lime	1940	chert or chat various	
shale lime shells	2049	colored shale	2960
shale & lime	2180		
lime & shale	2287	Total Depth	2960
lime	2390		
shale	2455		
gray shale	2475	Top of Kansas City	2475
light to tan chrystalline lime			
light oil stain at 2495-2500	2545		
light to tan chrystalline lime			
porous	2570		
light to tan chrystalline lime	2585		
black shale	2590		
light to gray lime	2600		
light to tan lime	2625		
light to tan oolitic lime	2640		
dark shale	2710		
dark and green shale	2715		
light to tan chrystalline lime	2730		
shale shells	2750		
light dense lime	2760		
gray shale	2785		
light lime	2790		
gray shale	2810		
light to tan lime	2820		
gray shale	2825		
light to tan lime	2840		
shale shells	2905		
various colored shale shells			
some red and orange colored			
chert or chat	2920		
TM 2917 Time log			
1/2 hr various colored and white			
chert or chat			
1 hr various colored and white			
chert or chat			
1 1/2 hr various colored and white			
chert or chat			
cable tools 2920-24 cement			
chert or chat sand and various			
colored shale	2930		
chert or chat sand and various			
colored shale	2935		

