




WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS CO.  
Farm - D. Dolbridge No. 1.

SEC. 28 T. 26 R. 2 E  
NW 1/4 NE 1/4  
330' FNL 330' FWL NE 1/4

Total Depth. 3563  
Comm. 5-9-46 Comp. 5-27-46  
Shot or Treated.  
Contractor. Kiowa Drlg. Co.  
Issued. 6-29-46

County. Sedgwick  
KANSAS



CASING:  
10 3/4" 198' LI Cem.

Elevation. \_\_\_\_\_

Production. Dry

Figures Indicate Bottom of Formations.

surface, clay & sand 35  
gyp & clay 90  
shale & lime 190  
lime & shale 220  
shale & sand 250  
lime 570  
shale 590  
lime & shale 1110  
shale & shells 1280  
shale 1400  
shale & lime 1540  
lime brkn 1662  
shale & lime 1975  
shale 2095  
shale & shells 2143  
lime 2190  
lime & shale lg t 2280  
lime 2300  
shale 2325  
lime 2340  
shale & lime strks 2405  
shale 2570  
lime 2770  
shale & little lime 2870  
lime 2900  
shale 2945  
chat 2968  
Miss. lime hrd 2995  
shale & chert 3015  
lime & chert 3069  
lime & shale 3088  
shale & chert 3098  
shale 3105  
lime hrd 3118  
lime sdy & shale 3140  
lime & shale 3172  
shale 3198  
shale & lime 3208  
shale 3286  
Viola 3306  
shale & lime 3344  
sand 3364  
shale 3580  
lime & shale 3406  
shale 3414  
lime 3450  
lime-little shale 3498  
lime sdy 3550  
lime 3563  
Total Depth

Tops:  
Kans. City Lime 2494  
Miss. 2944  
Chattanooga 3230  
Maquokata 3282  
Viola 3306  
Simpson 3352  
Arbuckle 3408

Run Drill Stem Test, set  
packer at 2945 - opened  
1 hr., rec. 150' fluid -  
60' oil cut mud and 90'  
salt water.

Run Schlumberger Survey at  
200' to 3563'

**PLUGGING**  
FILE SEC 28 T 26 R 2E  
PAGE 55 LINE 30

