


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sedgwick County. Sec. 29 Twp. 26 Rge. 2E (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines NW/4
Lease Owner Ray Law and Larry Moore Ranch, Inc.
Lease Name Jansen Well No. 1
Office Address McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 10-27- 19 54
Application for plugging filed August 19 54
Application for plugging approved _____ 19 _____
Plugging commenced September 6 19 54
Plugging completed September 9 19 54
Reason for abandonment of well or producing formation _____
Very little oil, too much water
If a producing well is abandoned, date of last production May 19 54
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Reul Durkee
Producing formation Burgess Sand Depth to top 2947 Bottom 2951 1/2 Total Depth of Well 2951 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5-1/2"		2545'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Filled hole with sand from 2951 1/2' to 2940'
and ran 6 sacks of cement. Pumped 30 sacks
of cement into surface pipe. Mudded hole to
2' and ran 5 sacks of cement on top. Plugging
completed.

RECEIVED
11-6-54
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.
Floyd E. Lietz (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Floyd E. Lietz
(Address) _____



SUBSCRIBED AND SWORN to before me this 5 day of Nov, 19 54
Carroll D. Winslow
Notary Public.

PLUGGING
FILE SEC 29 T 26 R 2E
PAGE 44 LINE 38

Well Log

Black and Hannum - Owners - Jansen No 1., Section 29, Township 26 South Range 2 East, Tract of land in Nw/4, commencing at NW Corner of Lot 2, thence South 1 1/4 rods, thence East 57-1/7 rods, thence North 1 1/4 rods thence West 57-1/7 rods to place of begining, Sedgwick County, Kansas

Spudded - 9-30-49
Completed - 10-27-49
Elevation - 1394'

Tops

Kansas City - 2502 ft.

Water Record

1/4 BW - 875 ft.
1/4 p.p.h. - 1425 - 1435 ft.
H.F.W - 1570 - 1585 ft.
H.F.W. - 2575 - 2590 ft.

Pipe Record

13-3/8" - 930 ft.
10" - 1605 ft.
8" - 2592 ft.
5-3/16" - 2947 ft.

PLUGGING
FILE SEC 29 T 26 R 2E
BOOK PAGE 64 LINE 38

RECEIVED
STATE CORPORATION COMMISSION
NOV - 6 1954
CONSERVATION DIVISION
Wichita, Kansas