

679

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1966
8-22-66

CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Tom - Kat - Inc

Complete Address: 1127 - Wichita Plaza - Wichita, Kas.

Lease Name Christu Well No. S.W.D.

Location nw - nw - sw - Sec. 29 Twp. 26 Rge. 2 (E) (W)

County Sedgwick Total Depth 2955

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kans. License No. 436

Operation Completed: Hour 1:45 Day 19 Month 8 Year 1966

The Above well was plugged as follows:

Filled hole with sand to 2862 ft.
Mixed & dumped 5 sacks of cement.
Pulled 2,501 ft. of 5 1/2" casing.
Set a 15 ft. Rock Bridge at 500 ft.
Added 20 sacks of cement.
Mudded hole to 35 ft. added 10 ft.
of Rock and 10 sacks of cement to surface.
(110 ft. of 8 5/8" surface pipe - circulated)

I hereby certify that the above well was plugged as herein stated.

Signed: Paul Embert
Well Plugging Supervisor

INVOICED Dellinger

DATE 8-22-66

INV. NO. 4865-E