

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01494-00-00
Spot: NENWSE Sec/Twnshp/Rge: 9-9S-17W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: THOMPSON Well #: 6
County: ROOKS Total Vertical Depth: 3541 feet

Operator License No.: 5375
Op Name: HILLENBURG OIL CO.
Address: 11600 S LYNN LN RD
BROKEN ARROW, OK 74011

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3539	0	125 SX
SURF	8.625	200	0	160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/04/2008 9:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: DANNY HILLENBURG Company: HILLENBURG OIL COMPANY Phone: (620) 628-4777

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 4% gel -500# hulls - 17 sxs gel spacer.
No squeeze records. Perforate anhy 1375'. Dakota 800'. 180' surface pipe.
Fluid 50' from surface. 115.08

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/04/2008 3:15 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

LK Wireline perforated two holes each at 1375' - 800' - 180'.
Ran tubing to 1656'. Hit bridge - washed thru - ran tubing to 3000'.
Allied pumped 17 sxs gel spacer, followed with 50 sxs cement with 100# hulls.
Pulled tubing to 800' - pumped 95 sxs 60/40 pozmix - 4% gel with 300# hulls - circulated cement.
PTOH. Pumped 50 sxs - circulated out 8 5/8" - shut in.
Squeezed 50 sxs down 5 1/2" casing.
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3524	3530		
3452	3458		
3404	3412		

INVOICED

DATE 8-29-08
INV. NO. 2007060305

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 20 2008

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

PPT

ALKAY OIL COMPANY

#6 THOMPSON

9-9-17W

NE NW SE

Contr. TRIANGLE DRLG

ROOKS County

E 2078RB Comm. _____ Comp. 6-19-59 IP

25 BOPD

Tops	Depth	Datum
ANH	1363	+715
HEEB	3181	-1103
TOR	3204	-1126
LANS	3223	-1145
BSL PENN SD	3465	-1387
ARB	3516	-1438
TD	3541	-1463

Casing
 8" 200
 5" 3539
 DST 3297-3313/1 HR, 320' SL OCV
 BHP 990#
 DST 3382-3410/1 HR, 55' O & GCM,
 60' MDY W, BHP 945#
 DST 3458-3518/1 HR, 35' H OCM,
 BHP 920#
 CO-3541: FRAC: ACID 2000
 NYRA POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS