

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21631-00-00  
Spot: N2S2NENE Sec/Twnshp/Rge: 20-31S-5W  
770 feet from N Section Line, 660 feet from E Section Line  
Lease Name: BLUBAUGH Well #: 1-20  
County: HARPER Total Vertical Depth: 4750 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	260		

154.38

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/08/2008 2:30 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JEREMY STUCKEY Company: MURFIN DRILLING Phone: (620) 353-8737

Proposed Plugging Method: 35 SKS ARB, 35 SKS 930', 35 SKS 600', 35 SKS 310', 25 SKS 60', 15 SKS RH

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE  
Date/Time Plugging Completed: 08/08/2008 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE DRL PIPE WAS RUN IN OPEN END TO THE TOP OF THE ARBUCKLE AT 4750, WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO THE BOTTOM OF THE SALT SECTION TO 930', WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 600' TO THE TOP OF THE SALT, WHERE 35 SKS OF CMT WAS SPOTTED. THE DRL PIPE WAS PULLED TO 60', WHERE 35 SKS OF CMT WAS SPOTTED. THE RAT HOLE WAS CIRCULATED WITH 15 SKS OF CMT.

Perfs:

INVOICED  
DATE 2/29/08  
INV. NO. 200 9060310

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 20 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CMTG 60/40 4% GEL

Plugged through: DP

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

PKT