

11-2

6 031451

API NUMBER 15-065-21086-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW NW _____, SEC. _____, T _____ S, R _____ W&E
4290 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____ 4767

Lease Name _____ Grecian P Well # _____ 1

Operator: Ritchie Exp Inc.
Name & Address: 1705 Anthony Drive
Hays, Ks 67601

County _____ Graham
Well Total Depth _____ 3825 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor _____ Ozzy's Well Service License Number _____

Address _____ Bogue, Ks .

Company to plug at: Hour: _____ Day: 2 Month: Nov Year: 19 90

Plugging proposal received from _____ John Nernberger

(company name) _____ Richie Exp (phone) _____

were: 8 5/8 set at 207 w/150 sks. 5 1/2 set at 3838 w/135 sks. PBDT 3700.

Perfs 3534 - 38. 3570-73; 5 1/2 sq at 1084 w/190 sks. New holes at 1150 - 1240.

Order 400 sks 65/35 poz 10% gel 500 lbs. hulls. Allied Cement Co. Rush Water Trucks.

Plugging Proposal Received by _____ Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 8:30 Day: 2 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT _____ Shot tubing and rods off at 3350 stripped out

rods and tubing to 2000 mixed and pumped thru tubing 130 sks cement blend to circ

to surface. Laid out tubing tied onto 5 1/2 and sq w/total of 155 sks to max

psi 1000 lbs. Close in psi 800 lbs. Sq 8 5/8 w/60 sks cement blend to max psi

500 lbs. Close in psi 500 lbs. Plug complete.

STATE CORPORATION COMMISSION

NOV 28 1990

11-28-1990

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED

(If you do not observe this plugging.

DATE 12-6-90

Signed _____ Carl Goodrow
(TECHNICIAN)

INV. NO. 30156

JAN 10 1991