

2 100256

8-5-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20,211-00-00

SE SW SW SEC. 8, T 26 S, R 2 W/E

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9913

Lease Name Tjaden Well # B-3

Operator: Bullseye Petroleum Inc
Name &

County Sedgwick 113.43

Address 9235 E. Harry, #15

Well Total Depth 3490 feet

Wichita, KS 67207

Conductor Pipe: Size 4 1/2" feet 3484 100 sxs

(316) 687-5280

Surface Casing: Size 8 5/8 feet 175 140 sxs

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated Perf 3370-71

Plugging Contractor Towanda Well Service, Inc. License Number 5683

Address P.O. Box 337, Towanda, KS 67144

Company to plug at: Hour: 4:00pm Day: 5 Month: 8 Year: 19 87

Plugging proposal received from William Ash

(company name) Bullseye Petroleum (phone) _____

were: Wood plug at 3300', and 15' rock bridge. Then dump 4 sxs cement. Shoot
and pull casing. Build 15' bridge at 300' and redimix to surface.

Plugging Proposal Received by Warren Kirkpatrick
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3:55 Day: 5 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT Wood plug at 3300' and 15' rock bridge. Dumped 4 sxs cement.

Shot 4 1/2" at 2479 and pulled out of well. Build 15' bridge at 300' and redi
mix to surface.

RECEIVED

STATE CORPORATION COMMISSION

AUG 12 1987
8-12-87

Remarks: Knebler Redimix #13553

CONSERVATION DIVISION
Wichita Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(If you did not observe this plugging.

DATE 8-14-87

INV. NO. 17830
8-5

WC

Signed Johnny Sanders
(TECHNICIAN)