

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-173-20572-00-00  
Spot: S2SWNWSW Sec/Twnshp/Rge: 8-26S-2E  
1650 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: TJADEN Well Number: 10  
County: SEDGWICK Total Vertical Depth: 3447 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 214  
Production: Size 5.5 feet: 3455 125 SX CMT  
Liner: Size \_\_\_\_\_ feet: 8/12.03

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2001 3:30 PM

Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.

Proposal Rcvd. from: DICK SCHREMMER Company: GRESSEL OILFIELD SERVICE, INC Phone: (316) 524-1225

Proposed Plugging Method: Sabd to 3,255' and top with 5 sxs.cement. Shoot pipe off and pull same. Run tubing to 265' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON

Witness Type: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 07/10/2001 5:15 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,240' and topped with 5 sxs. cement. Shot pipe off at 1,033' and pulled same. Ran tubing to 265' and circulated 75 sxs. cement to the surface. On 07/11/01 topped with 25 sxs. cement. Perforations from 3,304' to 3,424'.

RECEIVED  
KCC DISTRICT #2

JUL 12 2001

WICHITA, KS

INVOICED

DATE

7-12-01

INV. NO.

2002060047

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENTING. INVOICE #20776.

Plugged through: TBG

District: 02

Signed

Michael Wilson

(TECHNICIAN)