

2 030895

3-21

211 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20,201-00-00

SW SW SW, SEC. 8, T 26 S, R 2E W/E

330' feet from S section line
5950' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9913

Lease Name Tjaden Well # B-2

Operator: Bullseye Petroleum Inc.

County Sedgwick 113.17

Name & Address 15820 Plymouth

Well Total Depth 3482' P.B.T.D. 3336' feet

P. O. Box 781925

Conductor Pipe: Size 5-1/2" feet 3480'/125 sx

Wichita, KS 67278

Surface Casing: Size 8-5/8" feet 175' C.T.S.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pluggers, Inc. License Number 3909

Address 2316 S. Cypress, Wichita, KS 67207

Company to plug at: Hour: Day: 15 Month: 3 Year: 19 90

Plugging proposal received from Wiley Ash, Jr.

(company name) Pluggers, Inc. (phone) 316-688-1254

were: Rock 50' above perfs & 5 sx cmt - shoot & pull casing - set rock bridge
300' - cement to surface.

Perfs 3326' to 3330'

Plugging Proposal Received by Dist #2 (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: 21 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT Gravel hole to 3276' and dumped 5 sx cmt/bailer - shot
and pulled 2041' of 5-1/2" casing - set wood and rock bridge at 250' - Knebler
Concrete dumped 4-1/2 yds slurry mix to surface.

RECEIVED
STATE CORPORATION COMMISSION
4-4-90
APR 04 1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-18-90

Signed Don Thompson (TECHNICIAN)

INV. NO. 27884