

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-173-20280-00-00  
Spot: CW2NWSW Sec/Twnshp/Rge: 8-26S-2E  
990 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: TJADEN Well Number: 6-B  
County: SEDGWICK Total Vertical Depth: 3484 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 210  
Production: Size 4.5 feet: 3384 125 SX CMT  
Liner: Size \_\_\_\_\_ feet: 8/13.23

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/10/2001 1:00 PM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.  
Proposal Rcvd. from: DICK SCHREMMER Company: GRESSEL OILFIELD SERVICE, INC Phone: (316) 524-1225

Proposed Plugging Method: Sand to 3,275' and top with 4 sxs. cement. Shoot pipe off and pull same. Run tubing to 260' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 07/10/2001 2:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,245' and topped with 4 sxs. cement. Shot pipe off at 2,023' and pulled same. Ran tubing to 270' and circulated 75 sxs. cement to the surface. On 07/11/01 topped with 60 sxs. cement. Perforations from 3,324' to 3,345'.

**INVOICED**  
DATE 7-12-01  
INV. NO. 2002060047

RECEIVED  
KCC DISTRICT #2  
JUL 12 2001  
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENTING. INVOICE #20776.

Plugged through: TBG

District: 02

Signed Michael Wilson  
(TECHNICIAN)