

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-173-20225-00-00  
Spot: SESWSWSW Sec/Twnshp/Rge: 8-26S-2E  
1650 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: TJADEN Well Number: 4-B  
County: SEDGWICK Total Vertical Depth: 3450 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

Conductor Pipe: Size            feet:  
Surface Casing: Size 8.625    feet: 210  
Production: Size 5.5           feet: 3450    125 sx cmt  
Liner: Size                       feet:            8/12.13

Well Type: OIL                            UIC Docket No:                            Date/Time to Plug: 07/10/2001 12:00 PM  
Plug Co. License No.: 3004            Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.  
Proposal Rcvd. from: DICK SCHREMMER    Company: GRESSEL OILFIELD SERVICE, INC Phone: (316) 524-1225

Proposed Plugging Method: Sand to 2,905' and top with 5 sxs. cement. Shoot pipe off and pull same. Run tubing to 260' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON                            Witness Type: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 07/10/2001 1:00 PM                            KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2,900' and topped with 5 sxs. cement. Shot pipe off at 2,035' and pulled same. Ran tubing to 260' and circulated 70 sxs. cement to the surface. On 07/11/01 topped with 50 sxs. Cement.                            Perforations from 2,956' to 3,437'.

RECEIVED  
KCC DISTRICT #2  
JUL 12 2001  
WICHITA, KS

INVOICED  
DATE 7-12-01  
INV. NO. 2002060047

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENTING. INVOICE #20776.

Plugged through: TBG

District: 02

Signed Michael Reardon  
(TECHNICIAN)