

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20538-00-00
Spot: CSWNWSW Sec/Twnshp/Rge: 8-26S-2E
1650 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: TJADEN Well Number: 9-B
County: SEDGWICK Total Vertical Depth: 4339 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 212
Production: Size 5.5 feet: 4339 125 sx cmt
Liner: Size feet: 8/41.02

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/10/2001 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: DICK SCHREMMER Company: GRESSEL OILFIELD SERVICE, INC Phone: (316) 524-1225

Proposed Plugging Method: Sand to 3,255' and top with 5 sxs. cement. Shoot pipe off and pull same. Run tubing to 265' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 07/10/2001 10:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,190' and topped with 5 sxs. cement. Shot pipe off at 1,106' and pulled same. Ran tubing to 265' and circulated 70 sxs. cement to the surface. On 07/11/01 topped with 15 sxs. cement. Perforations from 3,306' to 3,428'.

RECEIVED
KCC DISTRICT #2

JUL 12 2001
7-12-01
WICHITA, KS

INVOICED

DATE 7-12-01

INV. NO. 2002060047

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENTING. INVOICE #20776.

Plugged through: TBG

District: 02

Signed _____
(TECHNICIAN)