

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-173-20817-00-00
Spot: CNWSWSW Sec/Twnshp/Rge: 8-26S-2E
990 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: TJADEN Well Number: C-2
County: SEDGWICK Total Vertical Depth: 3055 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 215 160 SX CMT
Production: Size 5.5 feet: 3480 10 SX CMT
Liner: Size _____ feet: 899.29

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/10/2001 2:30 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: DICK SCHREMMER Company: GRESSEL OILFIELD SERVICE, INC Phone: (316) 524-1225

Proposed Plugging Method: Sand to 3,005' and top with 5 sxs.cement. Shoot pipe off and pull same. Circualte cement from 265' to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 07/10/2001 3:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,000' and topped with 5 sxs. cement. Shot pipe off at 1,800' and pulled same. Ran tubing to 265' and circulated 75 sxs. cement to the surface. On 07/11/01 topped with 50 sxs. cement. C.I.B.P. at 3,055'.

RECEIVED
KCC DISTRICT #2

JUL 12 2001

WICHITA, KS

INVOICED

DATE 7-12-01

INV. NO. 2002060047

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENTING. INVOICE #20776.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)