

2 050778

9-19

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 173 20,793-GD-60

SW NE SW, SEC. 8, T 26 S, R 2 ~~W~~E

1650 feet from N/S section line

3480 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9913

Lease Name T. Jaden Well # C-1

Operator: Bullseye Petro. Inc.

County Sedgwick 113.10

Name & Address 9235 E. Harry, #15

Well Total Depth 3480 feet

Wichita, KS 67207

Conductor Pipe: Size feet

Surface Casing: Size 8-5/8 feet 254

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Jonathan License Number

Address Eldorado

Company to plug at: Hour: Day: 19 Month: 9 Year: 19 88

Plugging proposal received from

(company name) (phone)

were: 4-1/2" casing set @ 3479' - Perf @ 3456-60' - 3348-52 plug - 2998-3003'

Sand back to 2950' & dump 4 sx cement. Shoot & pull casing- bridge @ 290' to 270' and fill to surface w/redi mix.

Plugging Proposal Received by John (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:30 p Day: 19 Month: 9 Year: 1988

ACTUAL PLUGGING REPORT Sand back to 2950 and dumped 4 sx of cement w/dump bailer

shot and pulled 2423' of 4-1/2" casing - bridged surface hole from 270' to 290'

and filled to surface w/redi mix.

RECEIVED STATE CORPORATION COMMISSION STATE OF KANSAS

SEP 26 1988

9-26-88

CONSERVATION DIVISION Wichita, Kansas

Remarks: Knebler Redimix

If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 9-28-88

INV. NO. 22391

Signed Glenn L. Ward (TECHNICIAN)

9-19 DEC 9 1988