

3-23

2 030574

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20,279-00-00

SW SW NW, SEC. 8, T 26 S, R 2 WXE
2970 feet from N/S section line
4590 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3710

Lease Name Timmercamp Well # 2

Operator: Midco Energy, Inc.

County Sedgwick 112.78

Name & Address 8301 Lakeland Circle

Well Total Depth 3470 feet

Wichita, KS 67207

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Jonathan Oil Company License Number 4231

Address Eldorado, KS 67042

Company to plug at: Hour: 09:00 Day: 16 Month: 3 Year: 19 88

Plugging proposal received from Dick Krehbiel

(company name) Midco Energy, Inc. (phone)

were: Bottom plug 50' above perfs. 4 sxs cement. Shoot and pull 5 1/2" casing. Top plug 50' below bottom of surface casing. Cement to surface

Plugging Proposal Received by District #2 Office (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 18:15 Day: 23 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT Ran tools to 2933', gravel to 2863', dumped 6 sxs cement w/bailer.

Shot and pulled 2540' of 5 1/2" casing. Tried to set top plug--too much fluid in hole.

Moved rig to plug top later. 3-23-88 United Cementing #1387 pumped 3 sxs hulls, 6

sxs gel, 95 sxs 60/40 pozmix 4% gel down 8 5/8" casing. Pump pressure 600#

Shut in pressure 300#

RECEIVED
STATE CORPORATION COMMISSION
4-4-88
APR 4 1988

Remarks: CONSERVATION DIVISION Wichita, Kansas (If additional description is necessary, use BACK of this form.)

(If you did not observe this plugging.)

INVOICED

DATE 4-6-88

Signed Alan Thompson (TECHNICIAN)

WFV. NO. 20322

AUG 9 1988 SEP 13 1988