

2030172

API NUMBER 15-173-20,305-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW SE, SEC. 33, T 26 S, R 2 E
990' feet from W/S section line
1650' feet from E/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Winsley Well # 1

Operator: F+M Oil Co. Inc.

County Sedgwick 110.50

Name & Address 422 Union Center

Well Total Depth 3400 feet

Wichita, Ks. 67202

~~6 1/2" casing~~ Pipe: Size 5 1/2" feet 3380 150 5x

Surface Casing: Size 8 5/8" feet 240 190 5x

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Dual Completed

Plugging Contractor Kelso Casing Pulling License Number _____

Address Chase, Ks.

Company to plug at: Hour: 13:00 Day: 18 Month: 1 Year: 19 85

Plugging proposal received from Norman Voth

(company name) Kelso Casing Pulling (phone) _____

were: Sand hole to 2880', dump 6 ex cent, shoot + pull csg.
Of high fluid use 4 ex hulls, 12 ex gel, 115 ex cent.

Perfs 2938' to 2944' Open hole 3380' to 3400'

Plugging Proposal Received by Don Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 16:20 Day: 18 Month: 1 Year: 19 85

ACTUAL PLUGGING REPORT Sanded hole to 2880', dumped 6 ex cent. / bailed
shot + pulled 2412' of 5 1/2" csg. United Cementing # 7222
pumped 4 ex hulls, 12 ex gel, 115 ex cent. down 8 5/8" csg.
Pump Press. 600# S.I.P. 300#

RECEIVED
STATE CORPORATION COMMISSION
1-30-85
JAN 30 1985

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 2-7-85
INV. NO. 6872

W

Signed Don Thompson
(TECHNICIAN)

RO