

2 030825

6-29

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20,506-00-00
NE NE NE, SEC. 24, T 26 S, R 2 W/E
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5446

Lease Name Good Well # 1

Operator: Benjamin Giles

County Sedgwick 107.25

Name & Address 321 E. William

Well Total Depth 3300' PBTB 3260' feet

Wichita, KS 67202

Conductor Pipe: Size 5-1/2" feet 3297'/100 SX

Surface Casing: Size 8-5/8" feet 250' C.T.S.

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address P. O. Box 108, Geneseo, KS 67444

Company to plug at: Hour: Day: 15 Month: 6 Year: 19 88

Plugging proposal received from Allen Nicholas

(company name) Nicholas Casing Pulling (phone) 316-824-6467

were: Fill hole with sand to 3135' - dump 5 sx cement - shoot & pull 5-1/2" casing - set top bridge 300' - fill to surface with concrete.

Perf 3188' to 3189'

Plugging Proposal Received by Dist #2 (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 18:00 Day: 29 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT Filled hole/sand to 3135' - dumped 5 sx cement with

bailer - shot & pulled 2018' of 5-1/2" casing - could not bail hoel -

Consolidated Inc #80759 pumped 5 sx gel, 2 sx hulls, 100 sx 50/50 pozmix

4% gel down 8-5/8" casing - Pump press 350# - SIPress 100#

RECEIVED
STATE CORPORATION COMMISSION
7-24-89
JUL 24 1989

Remarks: (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(could) observe this plugging.

DATE 7-25-89

Signed Alon Thompson (TECHNICIAN)

INV. NO. 25409