

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20336-00-01

Spot: SESESE

Sec/Twnshp/Rge: 36-14S-15W

628 feet from S Section Line, 429 feet from E Section Line

Lease Name: HALL

Well #: 11

County: RUSSELL

Total Vertical Depth: 3207 feet

Operator License No.: 4058

Op Name: AMERICAN WARRIOR, INC.

Address: PO BOX 399

GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3207	0	125 SX
SURF		804	0	
T1	2.375	2900		

104.23

Well Type: EOR

UIC Docket No: E26889.1

Date/Time to Plug: 08/04/2008 8:30 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: JOE

Company: AMERICAN WARRIOR, INC.

Phone: (620) 275-7461

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 200# hulls. - 10 sxs gel spacer.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/04/2008 12:15 PM

KCC Agent: RAY DINKEL

**Actual Plugging Report:**

Ran tubing to 2803' - mixed 10 sxs gel spacer with 50 sxs 60/40 pozmix - 4% gel with 200# hulls - displaced with 5 BBL's of water.  
Pulled tubing to 823' - pumped approximately 100 sxs cement down tubing until we had good cement to surface.  
Pulled tubing out of well.  
Mixed good cement and filled 5 1/2" casing full.  
Hooked up to backside. Max. P.S.I. 500#. Little to no fluid pumped.

**Perfs:**

Top	Bot	Thru	Comments
3055	3058		
3012	3014		
2998	3000		
2977	2979		
2938	2941		

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 14 2008

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

Remarks: SWIFT SERVICES, INC.-TICKET #14319.

DATE 8/29/08

INV. NO. 2009060288

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Form CP-2/3

AUG 05 2008

36-14S-15W  
C E/2 SE SE

site: 4-1/2 S & 2 E OF GORHAM KS  
contr: EXPRESS WELL SVC  
prod: TOM LARSON

ay: RUSSELL  
field: GORHAM

API 15-167-20336

fr date 12/12/94      spd date 05/21/94      drig comp 05/21/94      card issued 12/12/94      last revised 12/12/94


```

ELV: 1784 KB, 1779 GL SMP
tops.....depth/ datum
ANH.....795 + 989
TOP.....2687 - 903
HEEB.....2910 - 1126
TOR.....2928 - 1144
LANS.....2969 - 1185
PBSD.....3170 - 1386
GORHAM SD.....3204 - 1420
ARB.....3206 - 1422
RTD OLD.....3209 - 1425

```

**IP status**

INJ, LKC 2938-3058 OA, 05/ 25/ 94

OLD INFO: OPERATOR WAS J L KING OIL OPER, 11 HALL, DEWEY, SPD 07/15/69, 07/21/69 8-5/8" 804 / 425 SX, 5-1/2" 3207 / 175 SX, OIL, P 50 BO & 50 BWPD, ARB 3207-3209, 08/21/69 (CARD ISSUED 08/28/69)

CONTR: RED TIGER DRLG

**NO CORES OR DSTS**

MICT - CO TO 3209 TD, (ARB OH), SO, NAT, POP, P 50  
BO & 50 BWPD. 8/21/69

NEW INFO: FR 12/12/94 , REWORKED 05/21/94 DC  
05/21/94 MICT - CO, SET CIBP AT 3170, PF (LKC) 2938-  
2941, 2977-2979, 2998-3000, 3012-3014, 3055-3058, SET 2-  
7/8" TBG AT 2892, PKR AT 2889, CONVERTED TO WIW -  
INJECTION RATE SATISFACTORY. 5/25/94

COPYRIGHT 1994  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS