

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20296-00-00
Spot: NESENE Sec/Twnshp/Rge: 34-19S-2W
3852 feet from S Section Line, 329 feet from E Section Line
Lease Name: KOEHN B Well #: 9
County: MCPHERSON Total Vertical Depth: 2985 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------------------|
| PROD | 4.5 | 2984 | | 30 SX |
| SURF | 8.625 | 140 | | 110 SX <u>97.01</u> |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/07/2008 9:30 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 628-4723

Proposed Plugging Method: SAND PERFS TO 2900' AND CAP WITH 4 SX'S CEMENT, RIP CASING @ 450' AND SET BRIDGE. CIRCULATE CEMENT FROM 450' TO SURFACE.

Plugging Proposal Received By: DAVE WERTZ Witness Type: PARTIAL
Date/Time Plugging Completed: 08/08/2008 10:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 2900' AND CAP WITH 4 SX'S CEMENT. PERFORATE CASING @ 450' AND PUMP CEMENT. LET SET FOR AWHILE - RETAGGED @ 400'. PUMP MORE CEMENT TO CIRCULATE CEMENT TO SURFACE. RUN 1" DOWN ON BACKSIDE OF PROD. CASING TO APPROX. 250' AND CIRCULATE CEMENT TO SURFACE. USED 133 MORE SX'S CEMENT ON 8-8-2008.

Perfs:

| Top | Bot | Thru | Comments |
|--|------|------|----------|
| 2956 | 2964 | | |
| INVOICED DATE <u>8/29/08</u> INV. NO. <u>2009060294</u> RECEIVED KANSAS CORPORATION COMMISSION AUG 20 2008 CONSERVATION DIVISION WICHITA, KS | | | |

Remarks: 60-40 POZ, 4% GEL. CONSOLIDATED TICKET #S 19093 AND 19094. LOG TECH TICKET #25913.

Plugged through: CSG

District: 02

Signed _____

Virgil Clothier
(TECHNICIAN)

PKY