

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03176-00-00
Spot: SESWSW Sec/Twnshp/Rge: 12-15S-18W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BROCK Well #: 4
County: ELLIS Total Vertical Depth: 3610 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3609	0	w/unknown sxs cmt
SURF	8.625	163	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/06/2008 2:00 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (620) 792-4745

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls - 18 sxs gel.
Operator said well was DV'd. 117.33

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/06/2008 6:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 3000'. Rigged to tubing - pumped 18 sxs gel followed with 50 sxs 60/40 pozmix and 200# hulls mixed in.
Pulled tubing to 1200'. Rigged to tubing - pumped 100 sxs 60/40 pozmix with 200# hulls to circulate cement to pit area.
Pulled tubing - topped off 5 1/2" casing with 15 sxs cement.
Hole standing full.
Rigged to 8 5/8" - pressured to 300# - instant pressure.

Perfs:

Top	Bot	Thru	Comments
3598	3602		

INVOICED

DATE 8/29/08
INV. NO. 2009060295

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 20 2008


Remarks: SWIFT CEMENTING COMPANY-TICKET #14346.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 04

Signed _____




(TECHNICIAN)

CM

Form CP-2/3

AUG 15 2008



DON E PRATT

#4 BROCK

12-15-18W
SE SW SW

Contr. EMPIRE DRLG ELLIS County


E. 2015 RE Comm. 3-11-55 IP 243 BOPD
PHY POT

Tops	Depth	Datum
HEEB	3242	-1227
TOR	3262	-1247
LANS	3291	-1276
CONG	3567	-1552
ARB	3598	-1583
ID	3610	-1595

Casing
8" 163
5" 3609

PERF 3598-3602: ACID 250;
17 BOPH/3 HRS

LEIKER POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS