

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21457-00-00
Spot: NWNENW Sec/Twnshp/Rge: 9-32S-21W
365 feet from N Section Line, 1455 feet from W Section Line
Lease Name: HARDIN Well #: 9A-3-5
County: CLARK Total Vertical Depth: 6500 feet

Operator License No.: 33060
Op Name: DIVERSIFIED OPERATING CORP.
Address: 15000 W 6TH AVE STE 102
GOLDEN, CO 80401

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5190		WITH 2 SX CMT
COND 20		100		GROUT
PROD 4.5		5301	2805	WITH 150 SX CMT
SURF 13.38		457		WITH 375 SX CMT

Well Type: GAS DH recept UIC Docket No: _____ Date/Time to Plug: 07/29/2008 9:30 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: JASON WALKER Company: _____ Phone: (620) 786-5600

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/30/2008 12:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

1ST PLUG SET CIBP @ 5190' & 2 SX CMT. 7/29/08: 2ND PLUG RIHWT & PUMP 15 SX GEL & 50 SX CMT AT 1000'. NO CIRCULATION. 3RD PLUG PULL TBG TO 504' & PUMP 50 SX CMT. NO CIRCULATION. 4TH PLUG PULL TBG TO 317' & PUMP 50 SX CMT. NO CIRCULATION. 5TH PLUG SHUT DOWN 4.5 HOURS. RAN TBG TO 1700'. PULLED BACK TO 1000' & PUMPED 75 SX CMT AT 1000'. SDFN. 7/30/08: 6TH PLUG RIH & TAGGED CMT AT 281'. PUMPED 150 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5220	5238		

INVOICED
DATE 8/29/08
INV. NO. 2009060297

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 18 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED
AUG 14 2008
KCC - WICHITA CITY

Signed Jerry W. Stapleton
(TECHNICIAN)
PIRT II

PIRT
Form CP-2/3