

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 32639
Name: CORAL PRODUCTION CORP.
Address: 1600 STOUT ST, SUITE 1500
City/State/Zip: DENVER, CO 80202
Purchaser: N/A
Operator Contact Person: JIM WEBER
Phone: (303) 623-3573
Contractor: Name: DISCOVERY DRILLING CO., INC.
License: 31548
Wellsite Geologist: TIM LAUER

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

<u>3/25/05</u>	<u>4/1/05</u>	<u>4/22/05</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 185-23294-00-00
County: STAFFORD
N/2 SW SW NW Sec. 25 Twp. 21 S. R. 14 East West
2120 feet from S (N) (circle one) Line of Section
350 feet from E (W) (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE (NW) SW
Lease Name: GERHARDT TRUST Well #: 1
Field Name: WILDCAT

Producing Formation: LANSING
Elevation: Ground: 1926' Kelly Bushing: 1934'
Total Depth: 3775' Plug Back Total Depth: 3772'
Amount of Surface Pipe Set and Cemented at 367 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

RECEIVED
MAY - 9 2005
KCC WICHITA

Drilling Fluid Management Plan AH 1 NCR 7-24-08
(Data must be collected from the Reserve Pit)


Chloride content 13000 ppm Fluid volume 295 bbls
Dewatering method used HAUL FEE FLUID

Location of fluid disposal if hauled offsite: _____
Operator Name: JOHN J. DORAH
Lease Name: ANSHUTZ #2SWD License No.: 5088
Quarter NE Sec. 15 Twp. 21 S. R. 14 East West
County: STAFFORD Docket No.: D-17893

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]
Title: PRESIDENT Date: 5/5/05
Subscribed and sworn to before me this 5 day of May
20 05.
Notary Public: [Signature]
Date Commission Expires: 2/1/2009



KCC Office Use ONLY

No Letter of Confidentiality Received
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

Operator Name: CORAL PRODUCTION CORP. Lease Name: GERHARDT TRUST Well #: 1
 Sec. 25 Twp. 21 S. R. 14 East West County: STAFFORD

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No
 Electric Log Run Yes No
 (Submit Copy)
 List All E. Logs Run:

Log Formation (Top), Depth and Datum Sample

Name	Top	Datum
HEEBNER	3279'	-1345'
LANSING	3408'	-1474'
BKC	3629'	-1695'
VIOLA	3670'	-1736'
ARBUCKLE	3762'	-1828'

DUAL INDUCTION LOG 3770'-SURFACE
 DENSITY NEUTRON 3748'-2800'
 MICRO LOG 3770'-2800'

RECEIVED
MAY - 9 2005
KCC WICHITA

CASING RECORD <input checked="" type="checkbox"/> New <input checked="" type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
SURFACE	12 1/4"	8 5/8" NEW	23	366'	COMM	300	3% CC, 2% GEL
PRODUCTION	7 7/8"	5 1/2" USED	14	3772'	ASC	150	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
2	3531'-3540'	3000 GAL 20% HCL ACID	3540'
2	3551'-3554'	1000 GAL 20% HCL ACID	3554'

TUBING RECORD	Size	Set At	Packer At	Liner Run
	2 7/8"	3701"		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No

Date of First, Resumerd Production, SWD or Enhr. 4/24/05 Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours Oil 52 Bbls. Gas Mcf Water tr Bbls. Gas-Oil Ratio Gravity

Disposition of Gas Vented Sold Used on Lease (If vented, Submit ACO-18.) METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

ORIGINAL

ALLIED CEMENTING CO., INC.

20057

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Crest Brand

DATE <u>3-25-05</u>	SEC <u>25</u>	TWP. <u>21</u>	RANGE <u>14W</u>	CALLED OUT <u>6:00 pm</u>	ON LOCATION <u>3:00 pm</u>	JOB START <u>10:30</u>	JOB FINISH <u>11:15 pm</u>
GERHARDT LEASE <u>Trust</u>		WELL # <u>#1</u>	LOCATION <u>Seward - 1/2 west - 2 south</u>		COUNTY <u>Stafford</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>NEW</u>			<u>1 west - 1/2 south - East into</u>				

CONTRACTOR Discovery Drilling

TYPE OF JOB Surface Pipe

HOLE SIZE 12 1/4 T.D. 369'

CASING SIZE 8 5/8 DEPTH 366'

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT 22 1/2

OWNER Coral Prods.

CEMENT

AMOUNT ORDERED 300 sq Common

3% c/c & 2% gel

COMMON	<u>300 sq.</u>	@	<u>8.30</u>	<u>2490.00</u>
POZMIX		@		
GEL	<u>6 gal</u>	@	<u>13.00</u>	<u>78.00</u>
CHLORIDE	<u>9 gal</u>	@	<u>36.00</u>	<u>324.00</u>
ASC		@		

EQUIPMENT

PUMP TRUCK # 120 CEMENTER Jack

BULK TRUCK # 344 DRIVER Don. D.

BULK TRUCK # _____ DRIVER _____

RECEIVED

MAY - 9 2005

KCC WICHITA

HANDLING	<u>315 gal</u>	@	<u>1.50</u>	<u>472.50</u>
MILEAGE	<u>315 New SS</u>	@	<u>16</u>	<u>277.28</u>
TOTAL				<u>3646.78</u>

REMARKS:

Run 9' of 8 5/8" casing - cement with 300 sq cement - Displace plug with 22 1/2 RBIs of Fresh water Cement did Circ.

Thanks

CHARGE TO: Coral Productions

STREET 1600 Stout St. Suite 1500

CITY Denver STATE Colo. ZIP 80202

SERVICE

DEPTH OF JOB 366'

PUMP TRUCK CHARGE 625.00

EXTRA FOOTAGE 66 @ .55 36.30

MILEAGE 16 @ 4.50 72.00

MANIFOLD _____ @ _____

TOTAL 733.30

PLUG & FLOAT EQUIPMENT

1-Top 8 5/8" Wood @ 55.00 55.00

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL 55.00

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Thomas Al

Thomas Al

PRINTED NAME

ALLIED CEMENTING CO., INC.

ORIGINAL

20061

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

MAY - 9 2005

SERVICE POINT:

Great Bend

KCC WICHITA

DATE <u>4-1-05</u>	SEC. <u>25</u>	TWP. <u>21</u>	RANGE <u>14w</u>	CALLED OUT <u>7:00 pm</u>	ON LOCATION <u>9:30 pm</u>	JOB START <u>Midnight</u>	JOB FINISH <u>1:00</u>
<u>Cerhardt</u> LEASE <u>Trust</u>	WELL # <u>#1</u>	LOCATION <u>Seward - 1/2 west - 2 north</u>			COUNTY <u>Stafford</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one)			<u>1 west - 3/4 north - 1/2 into.</u>				

CONTRACTOR Discovery Drilling

TYPE OF JOB Production string 5 1/2 csg

HOLE SIZE 7 7/8 T.D. 3775

CASING SIZE 5 1/2 DEPTH 3772

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL Break circ DEPTH _____

PRES. MAX 2500' MINIMUM _____

MEAS. LINE _____ SHOE JOINT 14

CEMENT LEFT IN CSG. 14' - Shoe

PERFS. _____

DISPLACEMENT 93 BBLs

OWNER Coral Production Corp

CEMENT
AMOUNT ORDERED 150.34 A.S.C.
4500 gal

COMMON	@		
POZMIX	@		
GEL	<u>344</u>	@ <u>13.00</u>	<u>39.00</u>
CHLORIDE	@		
ASC	<u>150 ML</u>	@ <u>10.25</u>	<u>1537.50</u>
SALT	<u>900 #</u>	@ <u>15.00</u>	<u>13500.00</u>
ASTUSH	<u>500 GAL</u>	@ <u>1.00</u>	<u>500.00</u>
HANDLING	<u>17/24</u>	@ <u>1.50</u>	<u>256.50</u>
MILEAGE	<u>17/24</u>	@ <u>14</u>	<u>168.00</u>
			TOTAL <u>26330.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Jack

120 HELPER T.O.

BULK TRUCK

341 DRIVER Steve

BULK TRUCK

_____ DRIVER _____

REMARKS:

Run 113 lbs of 5 1/2 csg - circ 20 min
mix 500 gal of mud flush - cement
Patch hole with 1500 cement - mix 1300
or cement down csg - Displace plug with 92
BBLs of fresh water - Plug landed @
1200 - held.

Thanks

CHARGE TO: Coral Production Corp
STREET 1600 Stout St. Suite 1500
CITY Denver STATE Colo ZIP 80202

SERVICE

DEPTH OF JOB	<u>3772'</u>		
PUMP TRUCK CHARGE			<u>1260.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>14</u>	@ <u>4.50</u>	<u>63.00</u>
MANIFOLD		@	
			TOTAL <u>1323.00</u>

PLUG & FLOAT EQUIPMENT

1-1/2 guide shoe		<u>160.00</u>	<u>160.00</u>
1-1/2 insert	@	<u>235.00</u>	<u>235.00</u>
5-7/8 centralizers	@	<u>50.00</u>	<u>250.00</u>
1-1/2 basket	@	<u>140.00</u>	<u>140.00</u>
1-1/2 rubber plug	@	<u>60.00</u>	<u>60.00</u>
			TOTAL <u>845.00</u>

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment
and furnish cementer and helper to assist owner or
contractor to do work as is listed. The above work was
done to satisfaction and supervision of owner agent or
contractor. I have read & understand the "TERMS AND
CONDITIONS" listed on the reverse side.

TAX _____
TOTAL CHARGE _____
DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE

Joe Borja

PRINTED NAME

Joe Borja