

2 030698

8-28

API NUMBER 15- 015-20,096-~~X00~~-01

SE SW NW, SEC. 5, T 26 S, R 3 ~~XXE~~

2970 feet from S section line

4290 feet from E section line

Lease Name Cunningham Well # 1

County Butler 107.25

Well Total Depth 3300 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8-5/8 feet 208'

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5215

Operator: Lee Phillips Oil Co.

Name & Address 125 N. Market, #1532

Wichita, KS 67202

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Berentz Drilling License Number 5892

Address Eureka, KS

Company to plug at: Hour: 06:00 Day: 28 Month: 8 Year: 19 88

Plugging proposal received from Kevin Huff

(company name) Berentz Drilling (phone) \_\_\_\_\_

were: Fill hole with mud - run drill pipe to 3285' - spot 35 sx cement - pull DP to 260' - spot 35 sx cement - pull DP to 60' - spot 25 sx cement - pump 10 sx cement in rat hole

Plugging Proposal Received by Don Thompson (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 09:15 Day: 28 Month: 8 Year: 1988

ACTUAL PLUGGING REPORT Filled hole/mud - ran DP to 3285' - Halliburton #745222-5

spotted 35 sx 60-40 posmix 2% gel - pulled DP to 250' - spotted 35 sx posmix - pulled DP pushed plug 60' spotted 25 sx 60-40 pos - pumped 10 sx 60-40 posmix in rathole.

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-15-88

INV. NO. 22262

Signed Don Thompson (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 12 1988  
CONSERVATION DIVISION  
Wichita, Kansas